

Date 09.02.2021

**Q U O T A T I O N**

**Sub: 02 Nos bore hole inside pond for rainwater harvesting system at Mohuldih Mines.**

Dear Sir,

You are invited to offer sealed quotation for the subject work schedule of quantity in duplicate) in the enclosed schedule of quantity based on the terms and conditions given below: -

1. E. M. D Shall not applicable.
2. Income Tax /Sales Tax/Service Tax /work tax, if applicable shall be recovered at source on gross value of the work executed as per norms of the Corporation and balance amount on this account shall be deposited by the contractor directly to sales tax/income tax authority.
3. Completion time of work: Total work should be completed within **01 (One) month**, from the date of commencement of work, which shall be within 03 days from the date of issue of work order.
4. The offer must be valid for six months from the date of tender opening, and no contractor shall be allowed to withdraw his/their offer within this period
5. There will be no defect liability period for this work.
6. The price quoted should be firm and no escalation on any account whatsoever will be entertained/paid by the Corporation.
7. Payment would be released by Jamshedpur/Jaduguda cheque.
8. First & final bill will be paid for this work.
9. The price quoted by tenderer should be firm and no escalation on any account what-so ever will be entertained /paid by the Corporation.
10. All the rates quoted by Tender shall be inclusive of cost of all materials, labour, tools, tackles, plant and machinery necessary to complete the work at no extra cost to corporation for any item.
11. No any carriage/transportation for any material except otherwise stated in schedule of quantities shall be paid by the department for this work. Contractor should quote their rates accordingly.
12. Quantity of an individual item may vary to any extent and be excluded altogether. Contractor will carryout all works up-to a total variation of  $\pm 10\%$  (ten) on the contract price and all quoted rates shall remain firm within this limit.
12. Quantity of an individual item may vary to any extent and be excluded altogether. Contractor will carryout all works up-to a total variation of  $\pm 10\%$  (ten) on the contract price and all quoted rates shall remain firm within this limit.

**13. Contractor must quote their rates against all the items in Schedule of quantities supplied along with this tender. If any contractor fails to quote any of the items, they have to execute without any payment.**

14. Scope of Work: Supplying, assembling, lowering and fixing in vertical position in borehole as per schedule.

15. Contractor has to follow guidelines of AERB (Atomic Energy Regulatory Board) issued time to time.

16. Quotations must be submitted in the enclosed schedule of quantity (original and two copies in Xerox of the same) duly signed along with seal of the agency. Duly filled quotations shall be submitted in a sealed envelope and to be deposited in the office of Manager (Per's), Turamdih up to **17.02.2021** (12.00 Noon) and will be opened on same day at 3.30 P.M at Turamdih.

**17. All other terms and conditions shall be applicable as per General conditions of UCIL's tender norms.**

Either in full or part thereof or to split up if necessary without assigning any reason whatsoever.

Thanking you,

Yours faithfully,  
For Uranium Corporation of India Ltd.

(N. Patil)  
DGM. (Civil)

Encl: Schedule of quantity – 1 set

C.c to:

- 1) G. M (Mines), TMD
- 2) Manager (Pers),TMD
- 3) Addl Manager (A/c), TMD

**Estimate for 02 No bore hole inside pond for rain water harvesting system at Mohuldih Mines**

<b>Item No.</b>	<b>Description of Item</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate in figure</b>	<b>Rate in wards</b>	<b>Amount</b>
1	Supplying, filling, spreading & levelling stone boulders ,gravel of size range 5 mm to 10mm, in the recharge pit, over the existing layer of boulders, in required thickness, for all leads & lifts, all complete as per direction of engineer-in-charge.	2	CuM			
2	Supplying, filling, spreading & levelling coarse sand of size range 1.5 mm to 2 mm in recharge pit, in required thickness over gravel layer, for all leads lifts, all complete as per direction of Engineer-In - charge.	2	CuM			
3	Supplying, filling, spreading & leveling stone boulders, pebbles of size range 5 cm to 20 cm, in recharge pit, in the required thickness, for all leads and lifts, all complete as per direction of Engineer-in-charge	2	CuM			
4	Supplying, assembling, lowering and fixing in vertical position in bore well, un-plasticized PVC medium well casing (CM) pipe of 150 mm nominal size dia, confirming to IS:12818, including required hire and labour charges, fitting & accessories etc. all complete, for all depths, as per direction of EIC.	40	Mtr.			
<b>Total including GST</b>						
<b>Rebate</b>						
<b>Total Estimated Cost</b>						