

URANIUM CORPORATION OF INDIA LIMITED
(Govt. of India Enterprise)
TURAMDIH MINES, EAST SINGHBHUM

No. UCIL/TMD/MM/CIV/2019/01

March 26, 2019

To

- a) M/s Sakti Construction
- b) M/s K. G. Enterprises
- c) M/s A. K. Enterprises
- d) M/s Prakash Kumar Singh

Q U O T A T I O N

Sub: Painting and renovation work of Turamdih Guest House.

Dear Sir,

You are invited to offer sealed quotation for the subject work schedule of quantity in duplicate) in the enclosed schedule of quantity based on the terms and conditions given below: -

1. The quoted rate(s) should be inclusive of all taxes, insurance charges and personnel protective equipment charges excluding GST. **GST will be reimbursed on production of actual against of documentary evidence . PF is also applicable as per the norms of UCIL.**
2. Completion time of work: Total work should be completed within **01 (One) Months**, from the date of commencement of work, which shall be within 01 day from the date of issue of LOI/work order.
3. The offer must be valid for six months from the date of tender opening, and no contractor shall be allowed to withdraw his/their offer within this period
4. There will be 06 (Six) months defect liability period for this work.
5. The price quoted should be firm and no escalation on any account whatsoever will be entertained/paid by the Corporation.
6. Payment would be released by Jamshedpur/Jaduguda cheque.
7. One R. A & final bill will be paid for this work.
8. All the rates quoted by Tender shall be inclusive of cost of all materials, labour, tools, tackles, plant and machinery necessary to complete the work at no extra cost to corporation for any item.
12. No any carriage/transportation for any material except otherwise stated in schedule of quantities shall be paid by the department for this work. Contractor should quote their rates accordingly.

13. Quantity of an individual item may vary to any extent and be excluded altogether. Contractor will carryout all works up-to a total variation of $\pm 10\%$ (Ten) on the contract price and all quoted rates shall remain firm within this limit.
- 14. Contractor must quote their rates against all the items in Schedule of quantities supplied along with this tender. If any contractor fails to quote any of the items, they have to execute without any payment.**
15. Scope of Work: Painting & renovation work of Turamdih Guest House
16. Contractor has to follow guidelines of AERB (Atomic Energy Regulatory Board) issued time to time.
17. Quotations must be submitted in the enclosed schedule of quantity (original and two copies in Xerox of the same) duly signed along with seal of the agency. Duly filled quotations shall be submitted in a sealed envelope and to be deposited in the office of Addl. Manager (Pers.), Turamdih up-to **02.04.2019** (12.00 Noon.) and will be opened on same day at 3.30 P.M at Turamdih.
- 18. All other terms and conditions shall be applicable as per General conditions of UCIL's tender norms.**

Either in full or part thereof or to split up if necessary without assigning any reason whatsoever.

Thanking you,

Yours faithfully,
For Uranium Corporation of India Ltd.

(N. Patil)
D. G. M (Civil)

Encl: Schedule of quantity – 1 set

Schedule of Quantity for: Painting and renovation work of Turamdih Guest House

Quotation No. UCIL/TMD/MM/CIV/2019/01dtd 26.03.2019

| Item No. | Description of item | Qty | Unit | Rate Rs. P | Rate in Words | Amount Rs. P |
|-----------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|-------------|-----------------------|----------------------|-------------------------|
| 1 | <p>Supplying and applying two (02) coats of white wash over old work at various elevations including preparation of surfaces, cleaning etc. complete with all materials, labour, tools and tackle etc., scaffolding work as per specifications and directions of Engineer-in-charge</p> <p>COMPOSITION</p> <p>i) Water @ 5 litres per Kg of lime for making cream. ii) Fevicol DDI @ 4 gm. Per litre of lime cream. iii) Robin Blue @ 2gm. Per Kg lime</p> | 400.00 | Sqm | | | |
| 2 | <p>Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade Old work (two or more coats applied @ 0.83 Ltr/10 sqm)</p> | 3000.00 | Sqm | | | |
| 3 | <p>Wall painting with acrylic emulsion paint having VOC (Volatile Organic Compound) content less than 50 grams/litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two coat</p> | 1650.00 | Sqm | | | |
| 4 | <p>Applying one coat of cement primer of approved brand and manufacture on wall surface as per the direction of Engineer-in-charge.</p> | 1650.00 | Sqm | | | |

| Item No. | Description of item | Qty | Unit | Rate Rs. P | Rate in Words | Amount Rs. P |
|-----------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|-------------|-------------------|----------------------|---------------------|
| 5 | Painting with synthetic enamel paint of approved brand and manufacture to give an even shade Two or more coats on old work as per the direction of EIC | 1500.00 | Sqm | | | |
| 6 | Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc complete as per the direction of Engineer-in-charge | 3400.00 | Sqm | | | |
| 7 | Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc complete as per the direction of EIC | 3650.00 | Sqm | | | |
| 8 | Providing and applying liquid wall putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete as per the direction of EIC | 200.00 | Sqm | | | |
| 9 | Repairs to plaster of thickness 12mm to 20mm in patches of area 2.5 sq. meters and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete including disposal of rubbish to the dumping ground within 50metres lead :With cement mortar 1:4 (1cement: 4 fine sand) as per the direction of EIC including cost of all materials. | 200.00 | Sqm | | | |

| Item No. | Description of item | Qty | Unit | Rate Rs. P | Rate in Words | Amount Rs. P |
|----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|------|---------------|---------------|-----------------|
| 10 | Painting (one or more coats) on rain water, soil, waste and vent pipes and fittings with synthetic enamel paint of approved brand and manufacture and required colour on old work as per the direction of EIC:100 mm dia | 100.00 | Mtr | | | |
| 11 | Floor polishing on terrazzo floor with wax polish of approved brand and manufactures complete as per the direction of Engineer-in-charge. | 200.00 | Sqm | | | |
| 12 | Renewing glass panes, with putty and glazing clips wherever necessary including racking out the old putty : Float glass panes of thickness 4 mm | 20.00 | Sqm | | | |
| 13 | Renewal of old putty of glass panes (Length) | 100.00 | Mtr | | | |
| 14 | Clearing grass and removal of the rubbish up to a distance of 50 m outside the periphery of the area cleared. | 2000.00 | Sqm | | | |
| | Total | | | | | |
| | Rebate if any in words (_____) | | | | % | |
| | Total | | | | | |

Total in words _____

Note: GST will be paid extra.