

N.I.T. No.: TMD/MIN- 692

“Miscellaneous Electrical Works at Underground Mines, Turamdih”

PRICE PART OF THE TENDER DOCUMENT

SCHEDULE- A

SCHEDULE OF QUANTITY

Schedule of Items for the Work "Miscellaneous Electrical Works at Underground Mines, Turamdih." of N.I.T. No.: TMD/MIN- 692					
S/ NO.	Description of work	Unit	Quantity	Rate (Rs)	Amount (Rs)
				in figure	in figure
1	Laying, dressing and securing of 1.1 KV grade 1X 3.5CX 185Sq. mm armoured Cu/Al cable in underground mines. This includes shifting of cable from Central Store/ Dept. Cable Yard to the site.	mtr	2500		
	Rate in words:				
2	Laying, dressing and securing of 1.1 KV grade 1X3.5CX120 Sq. mm armoured Aluminium cable in underground mines. This includes shifting of cable from Central Store/ Dept. Cable Yard to the site.	mtr	4000		
	Rate in words:				
3	Laying, dressing and securing of 1.1 KV grade 1X 3.5C /4C X 25/35 Sq.mm armoured Aluminium cable in underground mines. This includes shifting of cable from Central Store/ Dept. Cable Yard to the site.	mtr	2500		
	Rate in words:				
4	Laying, dressing and securing of 1.1 KV grade 1X 2 / 4C X 6/10/16 Sq.mm armoured Aluminium cable in underground mines. This includes shifting of cable from Central Store/ Dept. Cable Yard to the site.	mtr	4000		
	Rate in words:				

5	Laying, dressing and securing of 5/10/20/50 pair telephone cable in underground mines. This includes shifting of cable from Central Store/ Dept. Cable Yard to the site.	mtr	650		
	Rate in words:				
6	Dismantling and stacking of 1.1 KV grade 1X 3.5CX185 Sq. mm armoured Copper/Aluminium cable in underground mines . This includes shifting of dismantled cable from site to Under ground Cable Yard.	mtr	1500		
	Rate in words:				
7	Dismantling and stacking of 1.1 KV grade 1X 3.5CX120 Sq. mm armoured Aluminium cable in underground mines . This includes shifting of dismantled cable from site to Under ground Cable Yard.	mtr	3000		
	Rate in words:				
8	Dismantling and stacking of 1.1 KV grade 1X 3.5C/ 4CX 25/35 Sq. mm armoured Aluminium cable in underground mines . This includes shifting of dismantled cable from site to Under ground Cable Yard.	mtr	2000		
	Rate in words:				
9	Dismantling and stacking of 1.1 KV grade 1X 2C/ 4C X 6/10/16 Sq. mm armoured Aluminium cable in underground mines . This includes shifting of dismantled cable from site to Under ground Cable Yard.	mtr	2000		
	Rate in words:				
10	Erection of PDBS in underground mines. This includes shifting of PDBs from surface to underground at desire place at different levels.	Nos.	3		

	Rate in words:				
11	Shifting of Gate-End Box with MS Stand (Approx. total wt.- 250KG) from one place to another manually in U/G Mines at same levels.	Nos.	50		
	Rate in words:				
12	Fixing of mining type tube light/bulkhead/group shed fitting with cable glanding & connection at underground mines. This includes shifting of fittings from departmental store (surface/ underground mines) to the work site.	Nos.	100		
	Rate in words:				
13	Removal of mining type tube light/bulkhead/group shed fittings at underground mines. This includes shifting of removed fittings to the departmental store at mines.	Nos.	100		
	Rate in words:				
14	Shifting & placing of 50 HP/ 60 HP DOL/ Star-Delta starters from surface/ underground tool-room to the work site at underground mines.	Nos.	10		
	Rate in words:				
Grand Total = Rs.					
Rebate @ _____ % if any = Rs.					
Net Amount = Rs.					
In Words:					

Note: All the materials, as per the schedule of work shall be supplied by UCIL at free of cost to the contractor.