

Schedule of Quantity:- Drilling of one no bore hole at Turamdih Mill for drinking water.					
Sl. No.	DESCRIPTION	QTY.	UNITS	Rate	
				Rs.	P.
1	Drilling of 8" dia bore hole (8" dia finished from surface to bottom) in insertion of M.S. casing pipe up to 25 M including cost of all machinery, labour, tools and tackles, testing of bore hole for yield etc as per directions of Engineer-in-charge.	180.00	Meter		
				(Rupees)	
2	Supply of the following pipes at work site inclusive of all taxes, loading, transportation, unloading and stacking at site etc complete as per direction of Engineer-in-charge. . 8" dia MS pipe of 5mm thick	25.0	Meter		
				(Rupees)	
3	Supplying of submersibel pump of approved make KSB/CALAMA/KIRLOSKER and any type of Model, as per specifications and directions of Engineer-in-charge, as follow a) Submersible pump 17.5 HP UQD152/UMAG150-16/21	1.0	Set		
				(Rupees)	
4	Supplying 3 core flat 4mm 2 copper cable Finolex make quality as per directions of Engineer-in-charge.	300.0	Meter.		
				(Rupees)	
5	Supplying of Submersible Star-delta Starter Panel Premium model Cat. No. - CPSPDAJ415V of BCH Mark with Dry run protection Minilec make, as per directions of Engineer-in-charge.	1.00	Nos		0.0
				(Rupees)	
6	Supplying, fitting and installing of 50mm nominal bore dia G.I. Pipes Jindal makes	122.00	Meter		
				(Rupees)	
7	Supplying, fitting and installing the following accessories of approved make including cost of all materials, labour tools and tackles etc. complete as per directions of Engineer-in-charge.				
a)	2" dia Carbon-steel glove Valve KSB/Venus make	1.00	No.		
				(Rupees)	
b)	2" dia Carbon-steel Non-return Valve KSB make	1.00	No.		
				(Rupees)	
c)	c) M.S Clamp to hold 2" G.I pipe	2.00	No.		
				(Rupees)	
d)	d) Pressure Gauge 20 Kg/Cm2	1.00	No.		
				(Rupees)	
e)	e) G.I nipple 2" dia	2.00	No.		
				(Rupees)	
f)	f) G.I bend 2" dia	2.00	No.		
				(Rupees)	
g)	h) Bore well cover for 8" id aBore well	1.0	No.		
				(Rupees)	
h)	i) 1/2" dia P.V.C Rope	260.00	meter		
				(Rupees)	
	j)PVC tape10 roll, TOP cover Tape - 20 roll, M seal 30 Pkt	1.00	L.S.		
				(Rupees)	
8	Installation charge for above items in position and commissioning of the whole system as per specifications and directions of Engineer-in-charge	1.00	Nos.		0.0
				(Rupees)	

Total Amount Rs:
Rebate if any (%) Rs
Net amount in Rs :-