

PRICE BID					
Name of Work: - EXCAVATION / EXTRACTION OF URANIUM ORE AT BANDUHURANG OPENCAST MINE OF UCIL FOR A PERIOD OF TWO (02) MONTHS					
NIT No. BND/MIN-18(A)					
SCHEDULE OF QUANTITY (BOQ)					
Item no.	Description of Items	Qty.	Unit	Rate (Rs.) including GST	Amount (Rs.) including GST
A	B	C	D	E	F = C x E
1	Excavation of Ore with breaking arrangement by the contractor reduced to size -400 mm. This shall be inclusive of drilling for production, blasting, loading, transportation upto ground hopper of Turamdih Mill at a distance of 7 km (approx.) from loading face (including cost of POL), dumping, leveling, construction and maintenance of haul roads and dust suppression.	150,000	MT		

Note:

1	This work will involve equipment equivalent to 1 Excavator EC 380DL, 4-6 Tippers FMX 460, 2 Drill machine (4") dia, 2 Rock breaker EC 210D, 1 Dozer D80, 1 Wheel Loader L958F, 1 Water Sprinkler (Tanker with vehicle) 12 KL.
2	No any escalation will be paid against this work.
3	Total of 170 manpower including 120 local displaced manpower will be deployed in this work in skilled and semi-skilled category. Contractor has to retain minimum 120 persons in (semi-skilled and skilled category) from the local villagers to start the work.
4	Bonus @ 8.33%, PF and Insurance to be paid against this work.
5	Explosive, Detonator and Electricity will be supplied free of cost by UCIL.
6	Dewatering will be done by UCIL.